"THE REALITY ON THE GROUND"

OROVILLE CASE STUDY

26 AUGUST 2020

Presented by: David Serafini, P.E., G.E. SPD-DSPC

"The views, opinions and findings contained in this report are those of the authors(s) and should not be construed as an official Department of the Army position, policy or decision, unless so designated by other official documentation."



lear Bliltheads car e Das 4 Oats

EENTREBUED CONT JANKON CHRIST



FOUO - Contains Pre-Decisional Information - Do Not release

BACKGROUND

Oroville Dam:

- Located 65 miles north of Sacramento on the Feather River
- California's second largest reservoir (3.5 million acre-feet)
- Tallest earth-fill dam in the United States (770-feet)
- A multipurpose reservoir providing water supply, hydropower and flood control.
 - Contributes to the irrigation of 755,000 acres in the arid San Joaquin Valley
 - Generates 762 megawatts (MW).
 - Provides 750,000 acre feet or storage for flood control
 - Provides municipal supplies to some 25 million people
 - Max release at spillway design is 296,000 cfs
- Construction was completed in 1968.

Oroville Spillways:

- Flood Control Outlet crest El. 813.6
- Conservation pool El 850.0
- Emergency Spillway crest El 901.0

USACE Role:

 While USACE did not construct, design, nor build Oroville Dam or it's spillways, there is a federal interest in the project, as this is a Section 7 Dam (i.e. federal dollars were invested to provide flood control space in the reservoir).



of Engineers





PROJECT FEATURES



Features: Oroville Dam and Spillway Hyatt Powerhouse Thermolito Diversion Dam and Powerplant

Thermolito Power Canal

- Thermolito Forebay
- Thermolito Pumping Generating plant
- Thermolito Afterbay

US Army Corps of Engineers.

path of water



The Sacramento Bee

FLOOD CONTROL OUTLET (FCO)



03/24/16

The FCO has been used historically during the flood season. It is designed for routine flood releases of 150,000 cfs, and can release as much as 300,000 cfs.













North Sierra Precipitation: 8-Station Index, February 05, 2018

3-7 FEBRUARY 2017





3-7 Feb Release through FCO increased from 20,000 to 54,000 cfs
7 Feb Release increased to 54,500 cfs
DWR discovers plume of dirty water in spillway flow
Release cut back to 5200 cfs to inspect
Engineers discover large crater
Water surface reaches El 860 ft



8-9 FEBRUARY 2017



8 Feb

- DWR requested USACE technical assistance
- EOC activated
- FCO erosion worsened
- FCO test flows up to 30,000 cfs

9 Feb

- Larger than expected inflows peak at 190,000 cfs
- SPK Personnel deploy to DWR office to lend tech assistance as authorized under PL84-99



10-11 FEBRUARY 2017

10 Feb

- Spillway flow increased to 48,000 cfs
- SPK is standing by to provide the State with additional engineering and geotechnical experts as well as additional flood fight materials as needed.

11 Feb

- Emergency Spillway begins to flow at 8:00 pm for first time
- Spill across the 1,700-foot-wide crest and was expected to peak at 6,000 to 12,000 cfs





12-16 FEBRUARY 2017



12-16 Feb - FCO flow kept at 100,000 cfs. Pool drops from El. 901 to El. 862

13 Feb

 USACE (SPK) personnel deploy to Oroville to provide technical assistance for emergency response.

15 Feb

 USACE/RMC began coordination with DWR to determine mission needs and USACE support

12 Feb

- Butte County Sheriff ordered mandatory evacuation
- FCO flow increased to 100,000 cu ft/s
- Max pool elevation of 902.5
- Flow over emergency spillway ended at 2030 hrs







US Army Corps of Engineers.

INUNDATION AREA (2006) SUNNY DAY



Understanding of Inundation Zone(s)

- Full Dam Breach
- Component Failure
 or Breach
- Sensitivity to Warning/Evacuation Time





EMERGENCY SPILLWAY DAMAGE









EMERGENCY SPILLWAY DAMAGE

10





EMERGENCY SPILLWAY DAMAGE



FCO DAMAGE



wall from broken drain at 5th fence post behind spillway wall.

spillway (gaps, broken drain erosion on wall foundation, and spillway backcutting).









28 Feb 2017

Between 27 Feb and 17 Mar – removed 1.25 million cy of debris from the river.







1-16 March 2017

Debris Removal



17 Mar 2017



Operations after emergency repairs to draw reservoir down for construction





Gated Flood Control Spillways Construction Construction Comparisons

	1968	2018
Length of main spillway	3,055 feet	3,055 feet
Width of main spillway	178.75 feet As wide as a 12-lane freeway with center divider	178.75 feet As wide as a 12-lane freeway with center divider
Flow capacity	270,000 cubic feet per second	270,000 cubic feet per second (100,000 cts from Nov 2017 through January 2019)
Spillway Chute Concrete thickness	DESIGN: 1 feet, 3 inches minimum ACTUAL: 2 feet, 8 inches average	DESIGN: 4 foot, 6 inches minimum ACTUAL: 7 feet, 6 inches average
Spillway wall height	20 feet - 27 feet 1 foot thick at the top 2 feet, 4 inches thick at the base	20 feet - 34 feet 2 feet thick at the top 5 feet thick at the base
Piezometers	0	58
Reinforcing steel	Layers: 1 Diameter: 5/8 inch	LAYERS: 2 (top is epoxy-coated) DIAMETER: 1 inch
Underdrains	TYPE: Clay DIAMTER: 6 inch	TYPE: PVC DIAMETER: 8 inch
Slab Anchors	QUANTITY: Appx. 5,700 DEPTH: 5 feet deep	QUANTITY: Appx. 7,000 (epoxy-coated) DEPTH: 15 to 25 feet deep

The need to get a contractor(s) on site to start construction in the narrow window

Phased Approach using contract modifications

Took over an entire office floor at DWR







California Department of Water Resources | www.water.ca.gov/oroville-spillway | November 2017



Days to go until November 1, 2017 milestone





CONSTRUCTION SITE IN OCTOBER 2017







CONSTRUCTION SITE IN 2020









https://www.youtube.com/watch?v=xhKiq4DSLfY&list=PLeod6x87Tu6eVFnSyEtQeOVbxvSWywPlx